BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40944

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/28/2019-20, Date: 17.03.2020

Name of Work:Improvements to roads and Footpath in ward no 5 Jakkur

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar		
				In Figures		In Words
1	99	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification (5km lead = 57+2*1.28X5) As per the direction of Engineer incharge.	cum	693.1	68616.90	Rupees Six Hundred Ninety Three and Ten Paise Only
2	257.76	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. As per the direction of Engineer incharge.	cum	217.94	56176.21	Rupees Two Hundred Seventeen and Ninety Four Paise Only
3	572.8	Removing and resetting of kerb stones As per the direction of Engineer incharge.	M	110.17	63105.38	Rupees One Hundred Ten and Seventeen Paise Only
4	143.2	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. As per the direction of Engineer incharge.	cum	5907.79	845995.53	Rupees Five Thousand Nine Hundred Seven and Seventy Nine Paise Only
5	644.4	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. As per the direction of Engineer incharge.	sqm	2453.38	1580958.07	Rupees Two Thousand Four Hundred Fifty Three and Thirty Eight Paise Only
6	172.8	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge.	Nos	5687.82	982855.30	Rupees Five Thousand Six Hundred Eighty Seven and Eighty Two Paise Only
7	318	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. As per the direction of Engineer incharge.	sqm	454.02	144378.36	Rupees Four Hundred Fifty Four and Two Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92